

Design Brief

Proposed Design Brief for new structures:

Pavilion:

- Concrete block wall construction with prefinished wood exterior siding.
- Engineered wood truss roof. Exposed underside with painted finish.
- Prefinished ribbed metal roof (similar to the museum addition roof).
- Interior bathroom walls to be painted exposed concrete block.
- Interior of the storage room and electrical room, unfinished concrete block.
- Painted steel columns (see rendering for locations)
- Painted hollow metal doors, frames & windows (see floor plan for locations)

Performance Stage:

- Concrete slab on grade
- Painted steel columns to support the roof structure.
- Exposed painted steel beams
- Painted exposed roof deck
- Prefinished metal roof (similar to the museum addition roof)